

TRIM-LINE HOSPITAL CUBICLE TRACK SYSTEMS

DESIGN AND SPECIFICATIONS

Trim-Line Hospital Cubicle Track Systems provide adaptability to every privacy screening requirements. The one piece track sections for surface and suspended type installations have no internal track ways allowing quick and effective cleaning.

SPECIFICATIONS

Scope of Work

Complete hospital cubicle track systems as shown on the plans, schedules and as specified herein. Specify and list section numbers where related work is called for.

Materials

Hospital cubicle track system - (surface or suspended) shall be Trim-line System as manufactured by Westport Manufacturing. Surface Track System - tracks shall be one piece aluminum extrusion, alloy 6063 T-5 1" (25mm) wide and 5/8" (16mm) deep with carrier track extending continuously 1/2" (12.7mm) below. Track section shall be polished and anodized to ALCAN specification CEI AN 13um. Mounting clips shall be 6063 T-5 extruded aluminum alloy to interlock with the track section, Suspended Track System - track shall be one piece aluminum extrusion, alloy 6063 T-5 1" (25mm) O.D. x 3/4" (19mm) I.D. ribbed tube with carrier track extending continuously 1/2" (12.7mm) below. Track section shall be polished and anodized to ALCAN specification CEI AN 13um. Suspension tubing shall be aluminum extrusion, alloy 6063 T-5; 1" (25mm) O.D. with .065" (1.65mm) wall thickness, polished and anodized to ALCAN specifications CE/AN 13um. Support hardware fittings shall be cast aluminum alloy A-320 polished and anodized to ALCAN specifications CE/AN 6um. Mobile Track System - shall be suspended track section containing mobile glides operating below and carried by either suspended or surface track installation.

Accessory Fittings:

1. Glides - curtain glide shall be molded nylon
2. End Stops - press formed steel, chrome plated.
3. Wing straps - press formed steel, chrome plated.
4. Release Fittings - Delran fittings designed to release for prevention of injury to destruction of one's own interest. Release capabilities as per specifications.

INSTALLATION

General

Curtain cubicles shall be provided in a manner to screen each bed separately. The assembly of each unit shall be such that no straight track shall terminate at any point of a radius. A second bend shall be used to carry the curtain past a straight run of track to eliminate all possible gaps.

Suspended Track

All hanger assemblies shall be properly aligned and installation made rigid. Track shall be continuous without splices or joints; and connections into fittings shall be secured by self tapping counter sunk metal screws. Not exposed surface mounted joining plates shall be used.

Surface Track

Shall be mounted on the surface of the ceiling by internal locking clips and no screw heads or bolts shall be exposed. Clips to be screwed to surface of ceiling with fastening as required by the ceiling construction.

BRAND:

Westport Mfg Co Ltd

GENERAL NOTE:

PROJECT NAME:

GC / CLIENT:

PROJECT MANAGER:

DATE:

REV	REVISION	DATE
1.	RELEASE TO REVIEW	
2.		
3.		
4.		
5.		



WESTPORT MANUFACTURING

1122 SW MARINE DRIVE
VANCOUVER, BC
V6P 5Z3

www.west-port.com
604-261-9326
800-663-9587